


# versatile™ 4C Mailbox, 4C09S-02



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3" H x 12" W x 15" D	2
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1
PARCEL	PL5	17" H x 12" W x 15" D	1

- Notes:**
1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
    - a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - c. No patron (tenant) lock shall be positioned more than 67" AFF.
    - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
  2. This 4C mailbox can also be used for private applications.
  3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 1/8".

PRODUCT SERIES: **VERSATILE™ 4C FRONT LOAD MAILBOX**

<b>NATIONALMAILBOXES</b> — A DIVISION OF NMHP INC. — <i>North America's Commercial &amp; Residential Mailbox Leader!</i> Address: P.O. Box 13144, Wauwatosa, WI 53213 Phone Number: 1-800-676-5161 Website: www.NationalMailboxes.com	MODEL <b>4C09S-02</b>	REV <b>D</b>
	SCALE <b>NONE</b>	LAST REV. DATE <b>5/15/14</b>
	DRAWING NUMBER <b>4C09S-02CS</b>	DRAWN BY <b>RS</b>