
versatile™ 4C Mailbox, 4C13D-11



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.	
MAILBOX	MB2	6-1/2" H x 12" W x 15" D	9	
MAILBOX	MB3	10" H x 12" W x 15" D	2	
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1	

- 1. This module does NOT meet USPS STD-4C installation specification requirements as shown below:
 - a. At least one customer compartment shall be positioned less than 48" above finished floor
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox is to be used for private applications.
- 3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) $1\frac{1}{8}$ ".

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



Address: P.O Box 13144, Wauwatosa, WI 53213 Phone Number: 1-800-676-5161 Website: www.NationalMailboxes.com

	MODEL 4C13D-11		REV	В
)).	SCALE	NONE	5/15/2014	
r!	DRAWING	NUMBER		DRAWN BY
	4C	13D-11CS		AFD