


versatile™ 4C Mailbox, 4C15S-13



COMPARTMENT CHART

| DESCRIPTION | COMPARTMENT | COMPARTMENT SIZE | QTY. |
|---------------|-------------|--------------------------|------|
| MAILBOX | MB1 | 3" H x 12" W x 15" D | 13 |
| OUTGOING MAIL | OM2 | 6-1/2" H x 12" W x 15" D | 1 |

Notes:

- This module does NOT meet USPS STD-4C installation specification requirements as shown below:
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
- This 4C mailbox is to be used for private applications.
- The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1/8".

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



NATIONAL MAILBOXES

A DIVISION OF NMHP INC.

North America's Commercial & Residential Mailbox Leader!

Address: P.O. Box 13144, Wauwatosa, WI 53213

Phone Number: 1-800-676-5161

Website: www.NationalMailboxes.com

| | | | |
|----------------|------------|---------------|---------|
| MODEL | 4C15S-13 | REV | D |
| SCALE | NONE | LAST REV DATE | 5/15/14 |
| DRAWING NUMBER | 4C15S-13CS | DRAWN BY | RS |