
versatile™ 4C Mailbox, 4C16S-04



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.		
MAILBOX	MB2	6-1/2" H x 12" W x 15" D	3		
MAILBOX	MB3	10" H x 12" W x 15" D	1		
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1		
PARCEL LOCKER	PL15	15" H x 12" W x 15" D	1		

Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) $1\frac{1}{8}$ ".

PRODUCT SERIES:

VERSATILE™ 4C FRONT LOAD MAILBOX



Address: P.O Box 13144, Wauwatosa, WI 53213 Phone Number: 1-800-676-5161 Website: www.NationalMailboxes.com

	MODEL 4C16S-04		REV	В
	SCALE	NONE	LAST REV DATE 5/15/2014	
1	DRAWING	NUMBER		DRAWN BY
	4C	16S-04CS		SDH