


# versatile™ 4C Mailbox, 14 High Suite



## NOTES:

1. Below are the USPS STD-4C installation guidelines:

- At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
- No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
- No patron (tenant) lock shall be positioned more than 67" AFF.
- No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
- The USPS Arrow lock shall be positioned 36"- 48" AFF.

2. Modules noted with \* do not meet USPS STD-4C guidelines above.

PRODUCT SERIES: versatile™ 4C Mailbox 14 High Suite



MODEL	4C14H	REV	A
SCALE	NONE	LAST REV DATE	5/15/2014
DRAWING NUMBER	4C14HCS	DRAWN BY	AFD
		SHEET	1 OF 1