


# versatile™ 4C Mailbox 4CADD-09



COMPARTMENT CHART

| DESCRIPTION   | COMPARTMENT | COMPARTMENT SIZE      | QTY. |
|---------------|-------------|-----------------------|------|
| MAILBOX       | MB1         | 3" H x 12" W x 15" D  | 9    |
| OUTGOING MAIL | OM1         | 3" H x 12" W x 15" D  | 1    |
| PARCEL        | PL15        | 15" H x 12" W x 15" D | 2    |

**Notes:**

- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
  - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
  - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
  - No patron (tenant) lock shall be positioned more than 67" AFF.
  - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
  - The USPS Arrow lock shall be positioned 36"- 48" AFF.
- This 4C mailbox can also be used for private applications.
- The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1/8".

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



Address: P.O. Box 13144, Wauwatosa, WI 53213  
 Phone Number: 1-800-676-5161  
 Website: www.NationalMailboxes.com

|                |            |               |           |
|----------------|------------|---------------|-----------|
| MODEL          | 4CADD-09   | REV           | B         |
| SCALE          | NONE       | LAST REV DATE | 5/15/2014 |
| DRAWING NUMBER | 4CADD-09CS | DRAWN BY      | SDH       |